STANDARD OPERATING PROCEDURE SP05 FLORA AND FAUNA

ENVIRONMENTAL RISK ACTION PLAN					
Flora and Fauna					
Objective	• To comply with contractual and legislative requirements in relation to the community relations and complaints handling on the various project sites				
Legal, Contractual & Other Requirements	Contract Specification				
	See 3.2 Legal Requirements in EMS				
Targets	Nil damage to retain and protected species and communities				
	 Zero verifiable flora and fauna complaints relating to construction activities. 				
	Comply with construction contract conditions				
	Protection of drainage lines				
Responsibilities	Site Supervisor are required to ensure that the requirements of this standard operating procedure are implemented				
	 Subcontractors are required to ensure that the requirements of this standard operating procedure are implemented for their operations. 				
	 The Project Manager is responsible for providing updates on the status of the project to the relevant stakeholders. 				
Controls (means & resources)	 Only the area of ground immediately required for construction is permitted to be disturbed or used for construction related activities is storage, waste management parking or drainage. 				
	Minimise subcontractor / worker parking on site				
	 Identify locations for material storage, waste bins and site access to avoid unnecessary vegetation / tree removal 				
	 Erect perimeter fencing, protective measures and signage around vegetation and trees 				
	 Maintain protective measures to prevent damage to vegetation and monitor fenced off areas to prevent unauthorized construction activities (ie storage) 				
	Maintain vegetation / grass buffers along drainage lines				
	Prevent water				
	 Site Supervisor are to conduct inspections and complete the Daily Site Safety checklist Doc No: OHS013.14 to assess the condition of protective measures, the potential impact of work activities and any maintenance requirements / improvements 				
	 Inspect all trees and hollows immediately prior to clearing to identify any fauna using the tree/vegetation (details to be listed on the SWMS) 				
	 Undertake progressive stabilization of disturbed areas (eg covering, seeding or landscaping) 				
	 Progressively undertake stabilization and remediation works to reduce erosion 				
	 Engage an arborist in any works involving lopping, pruning or the cutting of roots of retained trees. 				
	 Report damage to retained or protected vegetation and trees to the Project Manager and Systems Manager. Work must cease in this area 				

ENVIRONMENTAL RISK ACTION PLAN					
Flora and Fauna					
	immediately.				
Timeframe	Duration of site works.				
Monitoring & Reporting	 Weekly inspections to be recorded on the Daily Site Safety Checklist Doc No: OHS013.14 				
	 Complaints to be recorded on form Environmental Incident and Complaint Report ENV026. 				
	 A register Incident / Accident Register Doc No: OHS052 will be maintained for all incidents or complaints. 				
	 Monthly project status briefs to be provided to the clients representative and stakeholders if required under the contract. 				
Review & Evaluation	• In order to ensure this procedure remains effective, it will be reviewed by Senior Management on an annual basis or in the event of a major environmental incident, changes in legislation or if raised by workers concern/s.				

Version Control

Date	Version	Owner	Comments
29.03.11	1	Michelle Murphy	For Issue
23.12.13	2	Michelle Murphy	Management Review
18.05.15	3	Michelle Murphy	Management Review
20.08.18	5	Michelle Murphy	ISO Accreditation Review
09.09.19	6	Michelle Murphy	Management Review
03.02.22	7	Michelle Murphy	Management Review
13.12.24	8	Michelle Murphy	Management Review